

Hotel

WinStar Hotel

Thackerville, OK

Client
WinStar Resort, LLC

Value
Confidential

Completion
2009

Assignment
Construction Management



Bovis Lend Lease is managing the construction of the 395-key WinStar Hotel, which includes a restaurant, bar-lounge, meeting rooms, spa, support function areas with associated sitework and landscaping.

The site work includes preparation, paving and curbs, excavation, site improvements, landscaping and irrigation.

Foundations include backfill, an auger cast piling foundation system, spread footings, grade beams, elevator pit walls and slab on grade.

The superstructure is structural concrete columns, shear walls and post-tensioned concrete. Exterior walls are light gauge metal stud backup with EFIS, FRP and accents, aluminum store fronts and windows. Roofing is modified bitumen and clay tile.

The building will also feature cultured marble, architectural cabinets with solid surface tops, concrete stairs with painted and galvanized metal balcony railings, ceramic tiling and geared traction elevators.